

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

1 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Permanent Facility				
1	CHEMICAL- BUILDING MATERIAL	Admixture	Ash Content	IS 9103
2	CHEMICAL- BUILDING MATERIAL	Admixture	Chloride	IS 6925
3	CHEMICAL- BUILDING MATERIAL	Admixture	Dry Material Content	IS 9103
4	CHEMICAL- BUILDING MATERIAL	Admixture	pH Value	IS 9103
5	CHEMICAL- BUILDING MATERIAL	Admixture	Relative Density	IS 9103
6	CHEMICAL- BUILDING MATERIAL	Bentonite	pH Value	IS 6186
7	CHEMICAL- BUILDING MATERIAL	Boulder Spalls (Petrography)	Sulphuric anhydride (SO ₃)	IS 4032
8	CHEMICAL- BUILDING MATERIAL	Cement	Alkali Content (Na ₂ O+0.658K ₂ O)	IS 4032
9	CHEMICAL- BUILDING MATERIAL	Cement	Aluminum Oxide (Al ₂ O ₃)	IS 4032
10	CHEMICAL- BUILDING MATERIAL	Cement	Calcium Oxide (CaO)	IS 4032
11	CHEMICAL- BUILDING MATERIAL	Cement	Chloride (Cl)	IS 4032
12	CHEMICAL- BUILDING MATERIAL	Cement	Drying Shrinkage	IS:4031
13	CHEMICAL- BUILDING MATERIAL	Cement	Free Lime	IS 4032
14	CHEMICAL- BUILDING MATERIAL	Cement	Insoluble residue including silica	IS 4032
15	CHEMICAL- BUILDING MATERIAL	Cement	Iron Oxide (Fe ₂ O ₃)	IS 4032
16	CHEMICAL- BUILDING MATERIAL	Cement	Loss on Ignition	IS 4032
17	CHEMICAL- BUILDING MATERIAL	Cement	Magnesium oxide(MgO)	IS 4032
18	CHEMICAL- BUILDING MATERIAL	Cement	Silica (SiO ₂)	IS 4032

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

2 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
19	CHEMICAL- BUILDING MATERIAL	Cement	Sulphur Trioxide(SO ₃)	IS 4032
20	CHEMICAL- BUILDING MATERIAL	Coarse & Fine Aggregate	Alkali Aggregate Reactivity- Rc	IS 2386 (Part 7)
21	CHEMICAL- BUILDING MATERIAL	Coarse & Fine Aggregate	Alkali Aggregate Reactivity-Sc	IS 2386 (Part 7)
22	CHEMICAL- BUILDING MATERIAL	Coarse & Fine Aggregate	Total Alkali Content As NA ₂ O	IS 4032
23	CHEMICAL- BUILDING MATERIAL	Coarse & Fine Aggregate	Total Sulphate Content As SO ₃	IS 4032
24	CHEMICAL- BUILDING MATERIAL	Coarse & Fine Aggregate	Water Soluble Chloride Content	IS 14959 (Part-2)
25	CHEMICAL- BUILDING MATERIAL	Concrete	Chloride in Fresh Concrete	IS 14959 Part-1
26	CHEMICAL- BUILDING MATERIAL	Concrete	Chloride in Hardened Concrete	IS 14959 Part-2
27	CHEMICAL- BUILDING MATERIAL	Fine Aggregate	Organic Impurities	IS 2386 (Part 2)
28	CHEMICAL- BUILDING MATERIAL	Fly Ash	Aluminum Oxide (Al ₂ O ₃)	IS 1727
29	CHEMICAL- BUILDING MATERIAL	Fly Ash	Chloride (Cl)	IS 4032
30	CHEMICAL- BUILDING MATERIAL	Fly Ash	Iron Oxide (Fe ₂ O ₃)	IS 1727
31	CHEMICAL- BUILDING MATERIAL	Fly Ash	Loss on Ignition	IS 1727
32	CHEMICAL- BUILDING MATERIAL	Fly Ash	Magnesium oxide(MgO)	IS 1727
33	CHEMICAL- BUILDING MATERIAL	Fly Ash	SiO ₂	IS 1727
34	CHEMICAL- BUILDING MATERIAL	Fly Ash	Sulphur as Sulphur Trioxide(SO ₃)	IS 1727
35	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Aluminum Oxide (Al ₂ O ₃)	IS 4032
36	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Calcium Oxide (CaO)	IS 4032
37	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Chloride (Cl)	IS 4032

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

3 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
38	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Insoluble Residue	IS 4032
39	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Loss on Ignition(LOI)	IS 4032
40	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Magnesium oxide(MgO)	IS 4032
41	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Silica (SiO ₂)	IS 4032
42	CHEMICAL- BUILDING MATERIAL	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Total Sulphate Content As SO ₃	IS 4032
43	CHEMICAL- BUILDING MATERIAL	Micro silica / Silica fume	Silicon Dioxide(SiO ₂)	IS 1727
44	CHEMICAL- BUILDING MATERIAL	Micro silica/ Silica fume	Alkalies as Na ₂ O	IS 4032
45	CHEMICAL- BUILDING MATERIAL	Micro silica/ Silica fume	Loss On Ignition	IS 1727
46	CHEMICAL- BUILDING MATERIAL	Micro silica/ Silica fume	Moisture Content	IS 15388
47	CHEMICAL- BUILDING MATERIAL	Soil/Sand	pH Value	IS 2720(Part-26)
48	CHEMICAL- BUILDING MATERIAL	Soil/Sand	Sulphate(as SO ₄)	IS 2720 (Part-27)
49	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Carbon (C)	ASTM E-415
50	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Carbon (C)	IS 8811
51	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Chromium(Cr)	ASTM E-415
52	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Chromium(Cr)	IS 8811
53	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Cobalt (Co)	ASTM E-415
54	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Cobalt (Co)	IS 8811
55	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Copper (Cu)	ASTM E-415
56	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Copper (Cu)	IS 8811



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

4 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
57	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Manganese (Mn)	ASTM E-415
58	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Manganese (Mn)	IS 8811
59	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Nickel(Ni)	ASTM E-415
60	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Nickel(Ni)	IS 8811
61	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Phosphorus (P)	ASTM E-415
62	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Phosphorus (P)	IS 8811
63	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Silicon (Si)	ASTM E-415
64	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Silicon (Si)	IS 8811
65	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Sulphur (S)	ASTM E-415
66	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Sulphur (S)	IS 8811
67	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Vanadium (V)	ASTM E-415
68	CHEMICAL- METALS & ALLOYS	Low Alloy Steel	Vanadium (V)	IS 8811
69	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Manganese (Mn)	ASTM E 1086
70	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Phosphorus (P)	ASTM E 1086
71	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Carbon (C)	ASTM E 1086
72	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Carbon (C)	IS 9879
73	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Chromium(Cr)	ASTM E 1086
74	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Chromium(Cr)	IS 9879
75	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Copper (Cu)	ASTM E 1086

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

5 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
76	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Copper (Cu)	IS 9879
77	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Manganese (Mn)	IS 9879
78	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Molybdenum(Mo)	ASTM E 1086
79	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Molybdenum(Mo)	IS 9879
80	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Nickel(Ni)	ASTM E 1086
81	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Nickel(Ni)	IS 9879
82	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Phosphorus (P)	IS 9879
83	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Silicon (Si)	ASTM E 1086
84	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Silicon (Si)	IS 9879
85	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Sulphur (S)	ASTM E 1086
86	CHEMICAL- METALS & ALLOYS	Stainless Steel Alloy	Sulphur (S)	IS 9879
87	CHEMICAL- WATER	Construction Water	Acidity	IS 3025 (Part-22)
88	CHEMICAL- WATER	Construction Water	Alkalinity	IS 3025(Part-23)
89	CHEMICAL- WATER	Construction Water	Chlorides (as Cl)	IS 3025(Part-32)
90	CHEMICAL- WATER	Construction Water	Fixed Residue	IS 3025(Part-18)
91	CHEMICAL- WATER	Construction Water	pH Value	IS 3025(Part-11)
92	CHEMICAL- WATER	Construction Water	Sulphate (SO3)	IS 3025 (Part-24)
93	CHEMICAL- WATER	Construction Water	Total Hardness	IS 3025(Part-21)
94	CHEMICAL- WATER	Construction Water	Total Suspended Solids	IS 3025(Part-17)
95	CHEMICAL- WATER	Construction Water	Volatile Residue	IS 3025(Part-18)
96	CHEMICAL- WATER	Water for construction purpose	Volume of 0.1 N HCl to neutralize 200 ml of sample (Alkalinity)	IRS-CBC-C.L.-4.3



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

6 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
97	CHEMICAL- WATER	Water for construction purpose	Volume of 0.1 N NaOH to neutralize 200 ml of sample (Acidity)	IRS-CBC-C.L.-4.3
98	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Compressive Strength	IS 6441, Part-5
99	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Density	IS 6441, Part 1
100	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Dimension -Length	IS 2185 ,Part-3
101	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Dimension -Length	IS 2185 : Part-3
102	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Dimension -Width	IS 2185, Part-3
103	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Dimension-Height	IS 2185 Part-3
104	MECHANICAL- BUILDINGS MATERIALS	Autoclave Areated Block	Drying Shrinkage	IS 6441, Part 2
105	MECHANICAL- BUILDINGS MATERIALS	Brick	Compressive Strength	IS 3495 (Part-1)
106	MECHANICAL- BUILDINGS MATERIALS	Brick	Efflorecence	IS 3495 (Part-3)
107	MECHANICAL- BUILDINGS MATERIALS	Brick	Sizes and Shapes (Height)	IS 1077
108	MECHANICAL- BUILDINGS MATERIALS	Brick	Sizes and Shapes (Length)	IS 1077
109	MECHANICAL- BUILDINGS MATERIALS	Brick	Sizes and Shapes (width)	IS 1077
110	MECHANICAL- BUILDINGS MATERIALS	Brick	Water Absorption	IS 3495 (Part-2)
111	MECHANICAL- BUILDINGS MATERIALS	Cement	Compressive Strength	IS 4031(Part 6)
112	MECHANICAL- BUILDINGS MATERIALS	Cement	Consistency	IS 4031 (Part 4)
113	MECHANICAL- BUILDINGS MATERIALS	Cement	Density	IS 4031(Part 11)
114	MECHANICAL- BUILDINGS MATERIALS	Cement	Drying Shrinkage	IS:4031 (Part 10)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD, CHANAKYAPURI, GOT, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 7 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
115	MECHANICAL- BUILDINGS MATERIALS	Cement	Final Setting Time (10 min. to 900 min.)	IS 4031 (Part-5)
116	MECHANICAL- BUILDINGS MATERIALS	Cement	Fineness by Blain Air Permeability	IS 4031 (Part 2)
117	MECHANICAL- BUILDINGS MATERIALS	Cement	Fineness by Dry Sieving	IS 4031 (Part-1)
118	MECHANICAL- BUILDINGS MATERIALS	Cement	Initial Setting Time (5 min. to 600 min.)	IS 4031(Part 5)
119	MECHANICAL- BUILDINGS MATERIALS	Cement	Soundness by Autoclave Method	IS 4031 (Part 3)
120	MECHANICAL- BUILDINGS MATERIALS	Cement	Soundness by Le Chatlier Method	IS 4031 (Part 3), Cl.5
121	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Dimension (Length)	IS 13630 : Part-1
122	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Dimension (Thickness)	IS 13630, Part-1
123	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Dimension (Width)	IS 13630, Part-1
124	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Modulus of Rupture	IS 13630 , Part-6
125	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Surface Quality	IS 13630 : Part-1
126	MECHANICAL- BUILDINGS MATERIALS	Ceramic Tiles	Water Absorption	IS 13630 : Part-2
127	MECHANICAL- BUILDINGS MATERIALS	Coarse & Fine Aggregate	Clay Lumps	IS 2386 (Part-2)
128	MECHANICAL- BUILDINGS MATERIALS	Coarse & Fine Aggregate	Coal & Lignite	IS 2386 (Part-2)
129	MECHANICAL- BUILDINGS MATERIALS	Coarse & Fine Aggregate	Soft Fragments (Soft Particles)	IS 2386 (Part-2)
130	MECHANICAL- BUILDINGS MATERIALS	Coarse & Fine Aggregate	Surface Moisture	IS 2386 Part 3
131	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	10% Fine Value	IS 2386 (Part-4)
132	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Abrasion Value	ASTM C131/C131M
133	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Abrasion Value	ASTMC535

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 8 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
134	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Abrasion Value	IS 2386 (Part-4)
135	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Bulk Density	ASTMC29/C29M-17a
136	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Bulk Density	IS:2386 (Part-3)
137	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Crushing Value	IS 2386 (Part-4)
138	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Elongation Index	IS 2386 (Part-1)
139	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Flakiness Index	IS 2386 (Part-1)
140	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Grading (Sieve Analysis)	IS 2386 (Part-1)
141	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Impact Value	IS 2386 (Part-4)
142	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Material Finer than 75 micron sieves	ASTM C117
143	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Material Finer than 75 micron sieves	IS 2386 (Part-1)
144	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Petrographic Examination	IS 2386 (Part-8)
145	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Soundness	ASTM C88/C88M
146	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Soundness	IS 2386 (Part-5)
147	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Specific Gravity	ASTM C127
148	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Specific Gravity	IS 2386 (Part-3)
149	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Water Absorption	ASTM C127
150	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregate	Water Absorption	IS 2386 (Part-3)
151	MECHANICAL- BUILDINGS MATERIALS	Coarse Aggregates	Grading (Sieve Analysis) (80mm - 0.075mm)	ASTM C136/C136M
152	MECHANICAL- BUILDINGS MATERIALS	Concrete	Drying Shrinkage & Moisture Movement	IS 1199

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :	SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD, CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA		
Accreditation Standard	ISO/IEC 17025:2017		
Certificate Number	TC-9050	Page No	9 of 20
Validity	01/12/2022 to 30/11/2024	Last Amended on	16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
153	MECHANICAL- BUILDINGS MATERIALS	Concrete	Drying Shrinkage & Moisture Movement	IS 516 (Part-6)
154	MECHANICAL- BUILDINGS MATERIALS	Concrete	Water Permeability of Concrete	IRS CBC, Appendix: G
155	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Air Content	IS 1199 : 1959 (part-4)
156	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Bleeding	IS 9103
157	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Compressive Strength	IS 516 (Part-1/Sec-1)
158	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Final Setting time	IS 1199 : Part-7
159	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Flexural strength	IS 516 (Part-1/Sec-1)
160	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Initial Setting time	IS 1199 : Part-7
161	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Length Change (Drying shrinkage)	IS:516- Part:6
162	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Water Content	IS 2386: Part-3
163	MECHANICAL- BUILDINGS MATERIALS	Concrete Admixtures	Workability (Slump)	IS 1199 (Part-2)
164	MECHANICAL- BUILDINGS MATERIALS	Concrete Curing Compound	Drying Time Requirement	ASTM C 309-03 Clause No. 10.3
165	MECHANICAL- BUILDINGS MATERIALS	Concrete Curing Compound	Water Retention Properties	ASTM C-156-98
166	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Bulk Density	IS 2386 (Part-3)
167	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Bulking of Fine Agg.	IS 2386 PART 3
168	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Grading (Sieve Analysis)	IS 2386 (Part-1)
169	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Grading (Sieve Analysis) (4.75mm-0.075mm)	ASTM C136/C136M
170	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Material Finer than 75 micron sieves	ASTM C117
171	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Material Finer than 75 micron sieves	IS 2386 (Part-1)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 10 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
172	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Petrographic Examination	IS 2386 (Part-8)
173	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Silt Content	CPWD Specification Vol-1 Chap.-3 Nabhi Publication
174	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Soundness	ASTM C88/C88M
175	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Soundness	IS 2386 (Part-5)
176	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Specific Gravity	ASTM C127
177	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Specific Gravity	IS 2386 (Part-3)
178	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Water Absorption	ASTM C-127
179	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregate	Water Absorption	IS 2386 (Part-3)
180	MECHANICAL- BUILDINGS MATERIALS	Fine Aggregates	Bulk Density	ASTM C29/C29M-17a
181	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Compressive Strength	IS 1727, Cl.10
182	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Drying Shrinkage	IS 1727, Cl.no.12
183	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Fineness by Blain Air Permeability	IS 1727, Cl.6.1
184	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Lime Reactivity	IS 1727, Cl.9
185	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Particles retained on 45 micron sieve	IS 1727, Cl.6.2
186	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Soundness by Autoclave Method	IS 4031 (Part 3), Cl.6
187	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Soundness by Le Chatelier Method	IS 4031 (Part 3), Cl.5
188	MECHANICAL- BUILDINGS MATERIALS	Fly Ash	Specific Gravity	IS 1727, Cl.15
189	MECHANICAL- BUILDINGS MATERIALS	Fresh Concrete	Slump	IS 1199 (Part 2) , Cl.4.3
190	MECHANICAL- BUILDINGS MATERIALS	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Fineness By Sp. Surface	IS 4031

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

11 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
191	MECHANICAL- BUILDINGS MATERIALS	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Moisture Content	IS 16714 Appendix-B
192	MECHANICAL- BUILDINGS MATERIALS	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Moisture Content	IS 16715 Appendix-B
193	MECHANICAL- BUILDINGS MATERIALS	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Slag Activity Index (SAI)	IS 16715 table-2, Note-2
194	MECHANICAL- BUILDINGS MATERIALS	Ground Granulated Blast Furnace Slag for Use in Cement, Mortar and Concrete	Slag Activity Index(SAI)	16714 table-2, Note-2: 2018
195	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete - Beam	Flexural Strength	IS 516
196	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete - Core	Rapid Chloride Ion Penetration	ASTM C 1202
197	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete Cube/Core	Compressive Strength	IS 516
198	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete Cube/Core	COMPRESSIVE STRENGTH OF ACCELERATED-CURED CONCRETE (Boiling Water Method)	IS:9013
199	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete Cube/Core	Density	IS:516 (Part 2/Sec1), Cl.4
200	MECHANICAL- BUILDINGS MATERIALS	Hardened Concrete Cube/Core	Depth of Water Penetration	IS 516 (Part 2/Sec 1)
201	MECHANICAL- BUILDINGS MATERIALS	Hollow/Solid Block	Compressive Strength	IS 2185 Part-1
202	MECHANICAL- BUILDINGS MATERIALS	Hollow/Solid Block	Density	IS 2185 Part-1
203	MECHANICAL- BUILDINGS MATERIALS	Hollow/Solid Block	Drying Shrinkage	IS 2185 Part-1
204	MECHANICAL- BUILDINGS MATERIALS	Hollow/Solid Block	Moisture Movement	IS 2185,Part-1
205	MECHANICAL- BUILDINGS MATERIALS	Hollow/Solid Block	Water Absorption	IS 2185 Part-1
206	MECHANICAL- BUILDINGS MATERIALS	Masonry Mortar	Compressive Strength of Masonry Mortar	IS 2250
207	MECHANICAL- BUILDINGS MATERIALS	Micro silica / Silica fume	Bulk Density	ASTM C-1240 - 10a, Cl. 19
208	MECHANICAL- BUILDINGS MATERIALS	Micro Silica / Silica Fume	Compressive Strength as percent at control sample	IS 1727

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

12 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
209	MECHANICAL- BUILDINGS MATERIALS	Micro silica / Silica fume	Specific Gravity	IS 1727
210	MECHANICAL- BUILDINGS MATERIALS	Micro Silica/Silica Fume	Over size percent Retained on 45 micron	IS 1727
211	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Abrasion Resistance	IS 15658
212	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Compressive Strength	IS 15658
213	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Dimensions -Length	IS 15658
214	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Dimensions-Thickness	IS 15658
215	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Dimensions-Width	IS 15658
216	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Flexural strength/Breaking Load	IS 15658
217	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Plan Area/Wearing face Area	IS 15658
218	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Tensile Splitting Strength	IS 15658
219	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Thickness of wearing layer	IS 15658 , Annexure B
220	MECHANICAL- BUILDINGS MATERIALS	Paver Block	Water Absorption	IS 15658
221	MECHANICAL- MECHANICAL PROPERTIES OF METALS	7 Wire strand	Nominal cross sec area of Strand	IS 14268
222	MECHANICAL- MECHANICAL PROPERTIES OF METALS	7 Wire Strand	Breaking Strength	IS 1608(Part 1)
223	MECHANICAL- MECHANICAL PROPERTIES OF METALS	7 wire strand	Elongation	IS 14268
224	MECHANICAL- MECHANICAL PROPERTIES OF METALS	7 Wire strand	Length of Lay	IS 14268
225	MECHANICAL- MECHANICAL PROPERTIES OF METALS	7 Wire strand	Nominal Diameter of Strand	IS 14268

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD, CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 13 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
226	MECHANICAL-MECHANICAL PROPERTIES OF METALS	7 wire strand	Nominal Mass	IS 14268
227	MECHANICAL-MECHANICAL PROPERTIES OF METALS	7 Wire strand	Percentage Difference in Diameter of Centre wire and Surrounding Wire of Strand	IS 14268
228	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Coupler	Tensile Test	IS-1608 P-1
229	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Ferrous Materials-Piping	Bend Test	IS 3589
230	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Fillet Weld Joints, Ferrous Product	Fracture Test	ASME Sec. IX
231	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Fusion welded joints and weld metal	Bend Test(Face bend and Root bend)	IS 3600 (Part-5)
232	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel	Mass per meter	IS 1786
233	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel	Rebend Test	IS 1786
234	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	0.2%Proof stress	IS 1608 (Part-1)
235	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	Bend Test	IS 1599
236	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	Elongation %	IS 1608(Part-1)
237	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	Tensile Strength	IS 1608 (Part-1)
238	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	Total Elongation % at max. force	IS 1608 (P-1)
239	MECHANICAL-MECHANICAL PROPERTIES OF METALS	Reinforcement Steel/Structural Steel	Yield Strength	IS:1608 (Part-1)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

14 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
240	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Spiral welded pipes	Bend Test(Face bend and Root bend)	IS 5504
241	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Weld and Welded specimen	Transverse Tensile Strength	IS 3600 (Part-3)
242	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Welded Steel Coupon Plate, Pipe and Weldments	Transverse Bend Test	ASME Sec.IX
243	MECHANICAL- MECHANICAL PROPERTIES OF METALS	Welded Steel Coupon Plate, Pipe and Weldments	Transverse Tensile Strength	ASME Sec.IX
244	MECHANICAL- SOIL AND ROCK	Bentonite	Dry Finess (75 micron)	IS 6186
245	MECHANICAL- SOIL AND ROCK	Bentonite	Dry Finess (150 micron)	IS 6186
246	MECHANICAL- SOIL AND ROCK	Bentonite	Free Swelling Index	IS 2720 : Part-40
247	MECHANICAL- SOIL AND ROCK	Bentonite	Gel Formation Index	IS 6186
248	MECHANICAL- SOIL AND ROCK	Bentonite	Liquid Limit	IS 2720 : Part 5
249	MECHANICAL- SOIL AND ROCK	Bentonite	Moisture Content	IS 6186
250	MECHANICAL- SOIL AND ROCK	Bentonite	Sand Content	IS 6186
251	MECHANICAL- SOIL AND ROCK	Bentonite	Slurry Density	ASTM D4380
252	MECHANICAL- SOIL AND ROCK	Bentonite	Specific Gravity	IS 2720 :Part-3 :Sec- 1
253	MECHANICAL- SOIL AND ROCK	Bentonite	Swell Power	IS 6186
254	MECHANICAL- SOIL AND ROCK	Bentonite	Viscosity - Marsh Cone Funnel	ASTM D6910
255	MECHANICAL- SOIL AND ROCK	Bentonite	Wet Finess (45 micron)	IS 6186
256	MECHANICAL- SOIL AND ROCK	Boulder Spalls (Petrography)	Petrographic Analysis	IS 2386 : Part-8

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

15 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
257	MECHANICAL- SOIL AND ROCK	Natural Building Stone	Apparent Specific Gravity	IS 1124
258	MECHANICAL- SOIL AND ROCK	Natural Building Stone	True Specific Gravity	IS 1122
259	MECHANICAL- SOIL AND ROCK	Natural Building Stones	Apparent Porosity	IS 1124
260	MECHANICAL- SOIL AND ROCK	Natural Building Stones	True Porosity	IS 1124
261	MECHANICAL- SOIL AND ROCK	Natural Building Stones	Water Absorption	IS 1124
262	MECHANICAL- SOIL AND ROCK	Polymer	Density	ASTM D4380
263	MECHANICAL- SOIL AND ROCK	Polymer	Viscosity	ASTM D-6910
264	MECHANICAL- SOIL AND ROCK	Rock	Density using Saturation and Buoyancy Technique	IS 13030, Cl.6
265	MECHANICAL- SOIL AND ROCK	Rock	Point Load Index	IS 8764
266	MECHANICAL- SOIL AND ROCK	Rock	Porosity using Saturation and Buoyancy Technique	IS 13030, Cl.6
267	MECHANICAL- SOIL AND ROCK	Rock	Slake Durability Index	IS 10050
268	MECHANICAL- SOIL AND ROCK	Rock	Specific Gravity	IS 13030
269	MECHANICAL- SOIL AND ROCK	Rock	Unconfined Compressive Strength	IS 9143
270	MECHANICAL- SOIL AND ROCK	Rock	Water Content	IS 13030, Cl.4
271	MECHANICAL- SOIL AND ROCK	Soil	Consolidation(Cc)	IS:2720 (Part 15)
272	MECHANICAL- SOIL AND ROCK	Soil	Consolidation(Pc)	IS:2720 (Part 15)
273	MECHANICAL- SOIL AND ROCK	Soil	Direct Shear Test (Angle of internal friction (f))	IS:2720 (Part 13)
274	MECHANICAL- SOIL AND ROCK	Soil	Direct Shear Test (Cohesion (Cc))	IS:2720 (Part 13)
275	MECHANICAL- SOIL AND ROCK	Soil	Free Swell Index	IS 2720 (Part 40)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

16 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
276	MECHANICAL- SOIL AND ROCK	Soil	Grain Size Analysis by Wet Sieving (0.075 to 4.75)	IS 2720 (Part 4), Cl.4.3.1
277	MECHANICAL- SOIL AND ROCK	Soil	Heavy Compaction - Maximum Dry Density	IS:2720 (Part 8)
278	MECHANICAL- SOIL AND ROCK	Soil	Heavy Compaction - Optimum Moisture Content	IS:2720 (Part 8)
279	MECHANICAL- SOIL AND ROCK	Soil	Hydrometer Test-Clay	IS 2720 :Part-4
280	MECHANICAL- SOIL AND ROCK	Soil	Hydrometer Test-Silt	IS:2720 (Part 4)
281	MECHANICAL- SOIL AND ROCK	Soil	Laboratory CBR Test (Soaked)	IS:2720 (Part 16)
282	MECHANICAL- SOIL AND ROCK	Soil	Laboratory CBR Test (Unsoaked)	IS:2720 (Part 16)
283	MECHANICAL- SOIL AND ROCK	Soil	Laboratory Permeability Test (Constant Head Method)	IS:2720 (Part 17)
284	MECHANICAL- SOIL AND ROCK	Soil	Laboratory Permeability Test (Falling Head Method)	IS:2720 (Part 17)
285	MECHANICAL- SOIL AND ROCK	Soil	Light Compaction - Maximum Dry Density	IS 2720 (Part 7)
286	MECHANICAL- SOIL AND ROCK	Soil	Light Compaction - Optimum Moisture Content	IS:2720 (Part 7)
287	MECHANICAL- SOIL AND ROCK	Soil	Liquid Limit	IS 2720 (Part 5)
288	MECHANICAL- SOIL AND ROCK	Soil	Plastic Limit	IS: 2720 (Part 5)
289	MECHANICAL- SOIL AND ROCK	Soil	Shrinkage Limit	IS:2720 (Part 6)
290	MECHANICAL- SOIL AND ROCK	Soil	Specific Gravity	IS 2720 (Part 3/Sec 1)
291	MECHANICAL- SOIL AND ROCK	Soil	Swelling Pressure	IS:2720 (Part 41)
292	MECHANICAL- SOIL AND ROCK	Soil	Traiaxial Test (T.C.D)- Angle of internal friction (F)	IS:2720 (Part 12)
293	MECHANICAL- SOIL AND ROCK	Soil	Traiaxial Test (T.C.D)- Cohesion (C)	IS:2720 (Part 12)
294	MECHANICAL- SOIL AND ROCK	Soil	Traiaxial Test (T.C.U) -Angle of internal friction (F)	IS:2720 (Part 12)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 17 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
295	MECHANICAL- SOIL AND ROCK	Soil	Traiaxial Test (T.C.U) -Cohesion (C)	IS:2720 (Part 12)
296	MECHANICAL- SOIL AND ROCK	Soil	Triaxial Test (T.U.U.) Angle of internal friction (f)	IS:2720 (Part 11)
297	MECHANICAL- SOIL AND ROCK	Soil	Triaxial Test (T.U.U.) Cohesion (C)	IS:2720 (Part 11)
298	MECHANICAL- SOIL AND ROCK	Soil	Unconfined Compressive Strength	IS:2720 (Part 10)
299	MECHANICAL- SOIL AND ROCK	Soil	Water Content	IS 2720 (Part-2)

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

18 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
Site Facility				
1	MECHANICAL- SOIL AND ROCK	Load Field Test	Cyclic Plate Load Test	IS 5249, Cl. 6
2	MECHANICAL- SOIL AND ROCK	Load Field Test	Lateral Load Test	IS 2911(Part-4) Cl. 8
3	MECHANICAL- SOIL AND ROCK	Load Field Test	Plate Load Test	IS 1888
4	MECHANICAL- SOIL AND ROCK	Load Field Test	Pull Out Test (Uplift)	IS 2911 Part-4 Cl. 9
5	MECHANICAL- SOIL AND ROCK	Load Field Test	Vertical Load Test(Compression) - Cyclic Load Method	IS 2911(Part-4) Cl. 7.3
6	MECHANICAL- SOIL AND ROCK	Load Field Test	Vertical Load Test(Compression) - Maintained Load Method	IS 2911(Part-4) Cl. 7.2
7	MECHANICAL- SOIL AND ROCK	Soil & Rock	Plate Load Test EV2/EV1	DIN 18134
8	MECHANICAL- SOIL AND ROCK	Soil & Rock -Field Test	Earth Resistivity Test (ERT)	IS 3043
9	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Field CBR Test	IS 2720(Part- 31)
10	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Field Density test by core cutter method	IS:2720 (Part 29)
11	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Field Density test by Sand replacement method	IS:2720 (Part 28)
12	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Field Moisture test by core cutter method	IS:2720 (Part 29)
13	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Field Moisture test by Sand replacement method	IS:2720 (Part 28)
14	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Modulus of Subgrade Reaction	IS 9214
15	MECHANICAL- SOIL AND ROCK	Soil Test At Site	Standard Penetration Test	IS:2131
16	NON-DESTRUCTIVE- BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Material -Reinforced Concrete Structure	Low Strain Pile Integrity Testing	IRC 78 : Appendix 7 :Part-2

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name :

SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard

ISO/IEC 17025:2017

Certificate Number

TC-9050

Page No

19 of 20

Validity

01/12/2022 to 30/11/2024

Last Amended on

16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
17	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Carbonation test	BS EN 14630
18	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Cover Meter	BS 1881 Part 204
19	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Half-Cell Potential Test	ASTM C 876
20	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Rebound Hammer	IS 13311 (Part 2)
21	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Ultrasonic Pulse Velocity	ASTM C-597
22	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Ultrasonic Pulse Velocity	IS 516 (Part 5/Sec.1)
23	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Bridge (Span) Load Test (Bituminous & Concrete Section)	IRC SP : 51
24	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	High Strain Pile Dynamic Test	ASTM D 4945
25	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	High Strain Pile Dynamic Test	IRC 78
26	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials - Reinforced Concrete Structures	Low Strain Impact Integrity Testing of Deep Foundations	ASTM D 5882
27	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials-Reinforced Concrete Structure	Carbonation Test	IS 516 :Part-5 : Section-3

NABL SCOPE



National Accreditation Board for Testing and Calibration Laboratories

SCOPE OF ACCREDITATION

Laboratory Name : SIMCON TECHNOLOGY PRIVATE LIMITED, 21, KRISHNA PARK, R. C. TECHNICAL ROAD,
CHANAKYAPURI, GOTA, AHMEDABAD, GUJARAT, INDIA

Accreditation Standard ISO/IEC 17025:2017

Certificate Number TC-9050

Validity 01/12/2022 to 30/11/2024

Page No 20 of 20

Last Amended on 16/12/2022

S.No	Discipline / Group	Materials or Products tested	Component, parameter or characteristic tested / Specific Test Performed / Tests or type of tests performed	Test Method Specification against which tests are performed and / or the techniques / equipment used
28	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials-Reinforced Concrete Structure	Half Cell Potential Test	IS 516 :Part-5 :Section-2
29	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Building Materials-Reinforced Concrete Structure	Rebound Hammer Test	IS 516 :Part-5: Section-4
30	NON-DESTRUCTIVE-BUILDING MATERIALS - REINFORCED CONCRETE STRUCTURES	Cross Hole Sonic Test on piles	Cross Hole Sonic Test	ASTM D 6760